3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs: 500 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for reconstructing an old black of the Barr Lines at Kolar," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer to the Government of Mysore who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The work should be executed as per specification.

10. All materials available from the old lines building or supplied by Government will have to be taken by the accepted tenders at rates fixed by the Executive Engineer.

Approximate estimate of quantities for reconstructing an old block of the Barr Lines at Kolar.

Serial No.	Items	Unit	Quantity
1	Earthwork excavation foundation and filling basement	C. yd.	336
2	Concrete in chunam	C. ft.	672
3	Burnt stone in clay	"	11,400
4	Burnt brick in clay	"	19,304
5	Burnt brick in mortar	"	3,062
6	Burnt stone slabs 6" thick, dressed	S. ft.	1,937
7	Chunam plastering	Sq.	41·45
8	Mud plastering	"	202·15
9	Chunam plastering, rough	"	160·75
10	Flooring with concrete and plastering	"	40·21
11	Burnt stone flagging and cement pointing	"	7·49
12	Flooring with gravel including lead	C. yd.	71
13	Honney wood work, wrought and put up	C. ft.	426·50
14	Do doors, battened, complete	S. ft.	1,612
15	Do windows do	"	312
16	Do pegs	Each	130
17	Roofing with Mangalore tiles on teak reepers, etc., complete	Sqr.	79·68
18	Ridge tiles set in mortar	R. ft.	192
19	Ventilating tiles	Each	104
20	Cornice, plain	R. ft.	78
21	Binding walls over gables	"	78
22	Silicate chocolate painting to doors and windows	Sq.	35·48
23	Honne wood eave board	R. ft.	384
24	Faning to wood work and bath and privy walls	Sq.	43·18
25	Providing seats in privy	Each	26
26	Coping with brick in mortar and plastering	R. ft.	1,177
27	U-shaped drain, complete, open	"	516
28	Do covered	"	40
29	Dismantling the existing roof and stocking materials ...	Sq.	56·12
30	Whitewashing	"	243·60
31	Colourwashing	"	160·75
32	Dismantling wall	C. ft.	20,508

V. V. KARVE,
Executive Engineer.

MYSORE HEADQUARTER RANGE.

Abstract Notification.

The attention of the public is invited to pages 1087 and 1088 of the *Mysore Gazette*, dated 12th December 1918, publishing the notice calling for tenders for the construction of out-houses in the European Guests' Quarters at Mysore.

GURURAO SIRSI,
Assistant Engineer.

HASSAN DIVISION.

Abstract Notification.

The attention of the public is invited to notification dated 12th December 1918, published in pages 1088 and 1089 of Part IV of the *Mysore Gazette* calling for tenders for Restoring Masavanghatta Tank, Channarayapatna Taluk.

The amount of earnest money to be deposited is Rs. 250 and the work should be completed by the end of December 1919.

R. W. SCALDWELL,
Executive Engineer.

KADUR DIVISION.

Dated Chikmagalur, 11th—12th December 1918.

A sum of Rs. 3-8-0, being the excess amount of rent recovered from Nagu Bai, wife of late Aswatha Rao, Head Munshi of Mudgere Taluk, towards the rent due from her husband,

is outstanding as due to the party whose wereabouts are not known. It is therefore hereby notified that if the amount is not claimed (by presenting a bill to this office for the refund of amount) within two months from this date, the same will be credited to Government.

K. PONNAPPA,
Executive Engineer.

CHITALDRUG DIVISION.

Dated 6th December 1918.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 4th January 1919, for restoring Kalgere Minor Tank, Registered No. 60 of Chitaldrug Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1920.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. to 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Kalgere Minor Tank, Registered No. 60, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Chitaldrug Division, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for Restoring Kalgere Tank, Registered No. 60 of Bharmasagara Hobli, Chitaldrug Taluk.

Item No.	Particulars	Per	Quantity
	Bund.		
1	Earthwork excavation and forming including lead watering and tamping, etc., works complete.	C. yd.	5,994
2	Forming grips, removing top soil strengthening breached portion, filling up scours, etc., complete.	Lump	sum Rs.
3	Gravel backing to revetment	C. yd.	585
4	Resetting old stone revetment with new jelly including lead, etc., complete...	"	1,115
5	Do new stone work	"	600
	Waste weir.		
6	Dismantling existing wall, etc.	C. ft.	250
7	Earthwork excavation	C. yd.	63
8	Concrete in surki mortar	C. ft.	488
9	Pointing in surki mortar	Sq.	18·04
10	Burnt stone in surki mortar	C. ft.	1,497
11	Burnt stone coping slabs over body wall including dressing, Chamfering the edges and lead jointing, etc.	S. ft.	348
	Wings.		
12	Rough stone work, old, resetting, etc.	C. yd.	40
13	New stone work with jelly and gravel backing	"	40
	Apron.		
14	Earthwork excavation using the earth to wings	C. yd.	110
15	New stone work with jelly and wedging	"	112
16	Burnt stone slabs 6" dressed	S. ft.	530
	Sluice.		
17	Cutting open the bund, examining and closing the leakages and building pucca cisterns, etc	Lump	sum Rs.
18	Clearing site and baling out water...	Lump	sum Rs.
	Sundries.		
19	Clearing jungle with roots, etc.	Lump	sum Rs.
20	Resetting old grade stones with new bed slabs to stand and level including cutting figures, numbering and painting, etc.	Each	20
21	Providing new grade stones complete, with bed slabs	"	13
22	Providing top width stones	"	33
23	Do gauge stones	"	3
24	Do register number stone	"	1
25	Do bench mark stones	"	2
26	Do date and year stone	"	1